



KENYA ELECTRICITY GENERATING COMPANY LIMITED

KGN-SEC-06-2017

**TENDER FOR DESIGN, CONSTRUCTION, FABRICATION AND INSTALLATION OF SECURITY
GATES, FENCES, GRILLS AND BARRIERS AT OLKARIA.**

11 January 2018

ADDENDUM 3 – FENCING WORKS AT OLKARIA 1 WORKSHOP

Bidders are required to include the following additional BOQ item in their Tender.

Item	description	Unit	quantity	Rate	Amount
J	Supply and fix 50mm dia, 2.5m high galvanised mild steel CHS poles into the concrete ground beam to support fence fabric as detailed in the typical drawing for the fencing works. Intermediate pole supports shall be fixed at the four corners, at mid points and at the gate structure location. The poles will be fixed with outriggers protruding outwards at 45 degrees and 300mm. The poles shall be spaced at 2.5m interval all around the 750m long fence. The contractor is required to supply all the fencing material and fix a 9 gauge galvanised fabric mesh 2.5m high, and Enhance fence by topping up with concertina barbed wire in coils, single strand, and 3mm dia. (At the workshops). The Contractor shall allow in his pricing for site clearance, topsoil stripping and construction of a toe beam around the 750m long (135 CM of class 25 Concrete including reinforcement fixed to detail provided in the typical drawing for the fencing works) fence as shown on the typical drawing for the fencing works.	M	750		

ACKNOWLEDGEMENT OF ADDENDUM 3

We, the undersigned hereby certify that the Addendum is an integral part of the document and has been incorporated in the tender document.

Signed

Tenderer:

Date