



KENYA ELECTRICITY GENERATING COMPANY PLC

KGN-GDD-098-2019
TENDER FOR DESIGN, SUPPLY, INSTALLATION AND TESTING OF ELECTRICAL POWER SUPPLY FROM OLKARIA 1 ADDITIONAL UNIT TO THE PROPOSED WELLHEAD CONTROL CENTER

Date: 3rd June 2019

CLARIFICATION No. 1

In accordance with the **TENDER FOR DESIGN, SUPPLY, INSTALLATION AND TESTING OF ELECTRICAL POWER SUPPLY FROM OLKARIA 1 ADDITIONAL UNIT TO THE PROPOSED WELLHEAD CONTROL CENTER**, KenGen hereby issues **Clarification No. 1**

No.	Bidders Question	KenGen's response
1.	Kindly clarify on the rating of the shielded 3-phase isolation transformer is it 200KVA or 350KVA and its costing in Price Schedule	The rating of the shielded 3-phase isolation transformer is 350KVA and its costing included in Price Schedule Section VII item 3 (Design, supply, test and commission Outdoor power supply distribution board
2	Kindly clarify on the outdoor main incomer MCCB rating, is it 500A or 400A	The rating of outdoor main incomer MCCB is 400A
3	Kindly clarify on costing of Fibre optic installation accessories which are missing on price schedule	The costing of fibre optic installation accessories is under Price Schedule Section VII item 4 (Supply of a 1.0KM armored Outdoor 24core single mode fibre optic cable)

ACKNOWLEDGEMENT OF CLARIFICATION No. 1

We, the undersigned hereby certify that the clarification is an integral part of the document and the alterations set out in the clarification have been incorporated in the tender proposal.

Signed.....

Tenderer.....

Date